EROSION CONTROL CONSTRUCTION NOTES

- (A) — INSTALL SANDBAGS (GRAVEL BAGS OPTIONAL) PER DETAIL ON SHEET C7.0 AND BMP SE–8.
- (B) — INSTALL SANDBAG (GRAVEL BAGS OPTIONAL) BERM PER DETAIL ON SHEET C7.0 AND BMP SE–8.
- (C) — INSTALL INLET PROTECTION PER DETAIL ON SHEET C7.0 AND PER BMP SE–8.
- (D) — INSTALL TEMPORARY ACCESS RAMP PER DETAIL ON SHEET C7.0 AT CONSTRUCTION ENTRY FOR SITE ACCESS.
- (E) — STABILIZED CONSTRUCTION ENTRANCE PER BMP TC–1.
- (F) — INSTALL SILT FENCE ALONG TOE OF SLOPE PER CASQA BMP SE–1

NOTES

1. THIS SHEET IS INTENDED FOR EROSION CONTROL PURPOSES ONLY.
2. SEE SHEETS C2.1 THROUGH C2.6 FOR GRADING AND SURFACE DRAINAGE.
3. SEE SHEET C7.0 FOR EROSION CONTROL GENERAL NOTES AND DETAILS.

DIGALERT
DIAL TOLL FREE
1-800-422-4133
AT LEAST TWO DAYS BEFORE YOU DIG
UNDERGROUND SERVICE ALERT OF SOUTHERN CALIFORNIA

0' 35' 70' 140'



KEY MAP NOT TO SCALE

MIG
MOORE IACOFANO GOLTSMAN, INC.
801 N. HARBOR BLVD.
FULLERTON, CA 92831
TEL 714/871-3538
FAX 714/871-1188
www.migcom.com

CONSULTANT:

PLANS PREPARED BY:
WALDEN & ASSOCIATES
CIVIL ENGINEERS · LAND SURVEYORS · PLANNERS
2552 WHITE ROAD · SUITE B, IRVINE, CA 92614
(949) 660-8118 · FAX (949) 660-8418

PROJECT TEAM:

LANDSCAPE ARCHITECT
MIG INC.

ARCHITECT
PITASSI ARCHITECTS INC.

CIVIL ENGINEERS/SURVEYOR
WALDEN & ASSOCIATES

STRUCTURAL ENGINEERS
CORREIA CONSULTING & DESIGN

ELECTRICAL ENGINEERS
LRA ENGINEERS

IRRIGATION DESIGNER
WILLIAMS IRRIGATION DESIGN

GEOTECHNICAL ENGINEERS
CONVERSE CONSULTANTS

TURF GRASS CONSULTANT
GUISE AND ASSOCIATES

PERRIS VALLEY Big League Dreams

2155 Trumble Road
Perris, California, 92570

SHEET TITLE

EROSION CONTROL PLAN

100% CONSTRUCTION DOCUMENT

DATE	REVISIONS

STAMP

REGISTERED PROFESSIONAL ENGINEER DAVID LEE BROWN No. 40496 Exp. 3-01-11 STATE OF CALIFORNIA

CHECKED BY	DATE
D.B.	01-07-10
DATE 01-07-10	FILE NAME
DRAWN BY B.A.	SHEET C7.1
JOB NO. 05208.00	
SCALE 1"=50'-0"	65 OF 313 SHEETS