MATERIAL SCHEDULE

ITEM	MANUFACTURER	SPECIFICATION	CONTACT	NOTES
BALLFIELD SCOREBOARD	FAIRPLAY SCOREBOARDS	MP-7114J-2	800-247-0265	FOREST GREEN SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION
SOCCER SCOREBOARD	FAIRPLAY SCOREBOARDS	HK-1600-4	800-247-0265	SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION
SOCCER SCORERS BOX @ DASHER WALL SYSTEM	SPORT SYSTEMS UNLIMITED		877-778-5911	SEE SHEET LD-5.1 - LD-5.3
SOCCER GOAL & NET @ DASHER WALL SYSTEM	SPORT SYSTEMS UNLIMITED		877-778-5911	SEE SHEET LD-5.1 - LD-5.3
SYNTHETIC TURF	SPORTEXE	MOMENTUM 41 2"	CRAIG EDWARDS 214-300-4004	SEE SHEET LD-5.1 - LD-5.3
SOCCER ARENA SHADE STRUCTURE	EMPIRE STEEL		858-362-0464	SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION
STADIUM LIGHTING	MUSCO LIGHTING		REFER TO ELECTRICAL PLANS.	SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION
STADIUM SEATING	TRACK SEATING	QT4-9; MODEL 4552 12LR	616-844-2471	ANGEL - FOREST GREEN FENWAY - FOREST GREEN DODGER - DODGER BLUE YANKEE - PERSIAN BLUE MINOR LEAGUE FIELDS -TAN
STADIUM SEATING (ADA)	TRACK SEATING	4552 -ARMLESS SPECTATOR	616-844-2471	COLORS INDICATED ABOVE - PER FIELD
SOCCER BLEACHERS	DANT-CLAYTON	ALUMINUM; 5 ROW X 26' WIDE	502-214-8709	POWDER COAT SEATS; SUBMIT COLORS FOR APPROVAL
BATTING CAGE PITCHING MACHINE	MASTER PITCHING MACHINE INC.	MA-5 W/ VIBRATOR	800-878-8228	
COIN BOX	MASTER PITCHING MACHINE		800-878-8228	
MONOPOLE - BATTING CAGE	NET SERVICES	45' INSTALLED HEIGHT	888-365-6387	SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION
BALLFIELD TEAM BENCH	DUMOR SITE FURNISHINGS	11-80 S-1	800-598-4018	COLOR: BLACK W/ RECYCLED PLASTIC CEDAR SLATS
FOUL BALL POLE	PATTERSON WILLIAMS	1274-30; YELLOW	800-669-2585	
INFIELD/WARNING TRACK MIX	GAIL MATERIALS	PRO-GOLD MIX WITH STABILIZER SOLUTION	951-667-6106	SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION
BAT RACK	TOMARK SPORTS	11814	800-959-1844	
BASE	BOLCO	175-MLB; WHITE	TOMARK SPORTS 800-959-1844	
BASE - DOUBLE	BOLCO	110-DBL; WHITE	TOMARK SPORTS 800-959-1844	
BASE - HOME	BOLCO	310-SHP; WHITE	TOMARK SPORTS 800-959-1844	
PITCHING RUBBER	HOLLYWOOD	BBPB	TOMARK SPORTS 800-959-1844	
PORTABLE PITCHING MOUND	TRUE PITCH	#302 - (6) TOTAL #202-B - (6) TOTAL #600-G - (6) TOTAL	TRUE PITCH 800-647-3569 CRAIG ALLISSON	
FIELD GRATE COVER	TOMARK SPORTS	TB-K13089	800-959-1844	COLOR: TBD SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION
SITE BENCH	DUMOR SITE FURNISHINGS	160-80	800-598-4018	COLOR: BLACK
PICNIC TABLE	FUSHION COATINGS, LANDSCAPE FUSION	F1105	800-231-1327	SHOP DRAWINGS COLOR: TBD
PLAZA PICNIC TABLE	LANDSCAPEFORMS	CAROUSEL TABLE. (5) BLACK POWDER COATED PERFORATED BACKED SEATS. TABLE TOP COLOR: BLACK STEELHEAD PERFORATED. W/ UMBRELLA HOLE	800-521-2546	SHOP DRAWINGS
MARKET UMBRELLA	LANDSCAPEFORMS	EQUINOX 8' UMBRELLA. POWDER COAT FRAME & POLE BLACK. FABRIC COLOR: OYSTER. PLAIN EDGE	800-521-2546	(UMBRELLAS NOT SHOWN ON PLANS)
TREE GRATE	SOUTH BAY FOUNDRY	D2272-SQ (72" SQ.)	619-456-2780	PROVIDE FRAME FOR INSTALLATION ADJACENT TO PAVERS. COLOR: POWDER COAT BLACK
TRASH RECEPTACLE	DUMOR SITE FURNISHINGS	107-32	800-598-4018	SHOP DRAWINGS COLOR: BLACK (TRASH RECEPTACLES NOT SHOWN ON PLANS)
DRINKING FOUNTAIN	MURDOCK	M-C76-1	800-453-7465	SHOP DRAWINGS COLOR: BLACK
DRINKING FOUNTAIN (HIGH/LOW)	MURDOCK	M-C76-2B	800-453-7465	SHOP DRAWINGS HIGH-LOW FOUNTAIN COLOR: BLACK

MATERIAL SCHEDULE

ITEM	MANUFACTURER	SPECIFICATION	CONTACT	NOTES
BIKE RACK	PATTERSON WILLIAMS	1602-09	800-669-2585	SHOP DRAWINGS COLOR: BLACK POWDER COAT
SITE FLAG POLES	LA STEELCRAFT PASADENA, CA	EC60 - AMERICAN FLAG EC40 - STATE FLAG	626-798-7401	SHOP DRAWINGS FINISH: GALVANIZED
ANGEL STADIUM FLAG POLES	LA STEELCRAFT PASADENA, CA	(2) EC25 (1)EC35	626-798-7401	3 TOTAL: TWO(2) 25' - GALVANIZED ONE(1) 35' - MED. BRONZE
BRICK PAVING	ORCO BLOCK	PAVER: ANTIQUE COBBLE COLOR: CHATEAU (B9) PATTERN: STAGGERED BOND WITH 5.5 X 8.25	AVAIL.: KRC ROCK 1-760-744-1036 CONTACT: ISAAC HAUFU	60 MM SIZE X 5.5 X 8.25 RECTANGLE. SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION
CONCRETE #1 - 4" THICK		COLOR: NATURAL GRAY MEDIUM BROOM FINISH		SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION
CONCRETE #2 - 6" THICK	DAVIS COLORS	COLOR: RUSTIC BROWN 6058, MEDIUM SAND BLAST FINISH	323-269-7311	SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION
CONCRETE #3 - 6" THICK		COLOR: NATURAL GRAY MEDIUM BROOM FINISH		SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION
CONCRETE #4 - 4" THICK	DAVIS COLORS	COLOR: RUSTIC BROWN 6058, MEDIUM SAND BLAST FINISH	323-269-7311	SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION
CONCRETE #5 - 6" THICK	DAVIS COLORS	COLOR: BRICK RED 160 W/ SEEDED 'RED' GLASS CHIPS	323-269-7311	SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION
CONCRETE #6 - 6" THICK	DAVIS COLORS	COLOR: DUNE 6058 MEDIUM BROOM FINISH	323-269-7311	SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION
PLAYGROUND RUBBERIZED SURFACING COLOR #1	SPECTRATURF	COLOR: 50/50 SPECTRA 1405 BLUE & 1407 NAVY (POURED IN PLACE)	951-736-3579	REFER TO PLANS FOR PATTERNS. SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION
PLAYGROUND RUBBERIZED SURFACING COLOR #2	SPECTRATURF	COLOR: 50/50 SPECTRA 1403 LIGHT BLUE & 2040 TEAL (POURED IN PLACE)	951-736-3579	REFER TO PLANS FOR PATTERNS. SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION
PLAYGROUND RUBBERIZED SURFACING COLOR #3	SPECTRATURF	COLOR: 50/50 SPECTRA 1612 GREEN & 1610 ARMY (POURED IN PLACE)	951-736-3579	REFER TO PLANS FOR PATTERNS. SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION
PLAYGROUND RUBBERIZED SURFACING COLOR #4	SPECTRATURF	COLOR: 33/33/33 SPECTRA 1102 EGGSHELL/1610 ARMY/2040 TEAL (POURED IN PLACE)	951-736-3579	REFER TO PLANS FOR PATTERNS. SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION
PLAYGROUND EQUIPMENT	LANDSCAPE STRUCTURES	AREA #1: 11934545-2-1 AREA #2: 11934545-1-1	COAST REG. 714-619-0100 GREGG ROGERS	SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION
70' HIGH SAFETY NETTING	NET SERVICES	K-36T 1-3/4"	888-365-6387	SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION
20' HIGH SAFETY NETTING	NET SERVICES	K-36T 1-3/4"	888-365-6387	SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION
BACKSTOP NETTING	NET SERVICES		888-365-6387	SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION
SHADE STRUCTURE TOT LOT #1	USA SHADE		CONTACT: PATTI ABRECHT 800-507-4233	SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION DETAIL 'C', SHEET LD-1.6
SHADE STRUCTURE TOT LOT #2	USA SHADE		CONTACT: PATTI ABRECHT 800-507-4233	SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION DETAIL 'A', SHEET LD-1.6
SHADE STRUCTURE @ MINOR LEAGUE FIELDS	USA SHADE		CONTACT: PATTI ABRECHT 800-507-4233	SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION DETAIL 'B', SHEET LD-1.6
WINDSCREEN FOR CHAIN LINK FENCE	FENCE PRO	OPEN MESH, VINYL COATED. MODEL: TB-K15247 COLOR: TBD	TOMARK SPORTS 800-959-1844	SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION.
DECORATIVE BOULDERS	KRC ROCK	ARTISIAN BOULDER #23BDR0176	760-744-1036 CONTACT: ISAAC HAUFU	SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION.
DECORATIVE FLAGSTONE	KRC ROCK	BLACKGOLD - 2" SLAB FLAGSTONE	760-744-1036 CONTACT: ISAAC HAUFU	SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION.
DECORATIVE ROCK COBBLE	KRC ROCK	RIVERSIDE RIVER ROCK	760-744-1036 CONTACT: ISAAC HAUFU	SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION.
STABILIZED DECOMPOSED GRANITE	KRC ROCK	COYOTE GOLD	760-744-1036 CONTACT: ISAAC HAUFU	SUBMIT SAMPLE FOR APPROVAL PRIOR TO INSTALLATION.

NOTE:
QUANTITIES AND MATERIALS PROVIDED ON THE MATERIAL LIST ARE FOR THE CONVENIENCE OF THE CONTRACTOR ONLY. ALL QUANTITIES AND MATERIALS SHOULD BE VERIFIED WITH THE PLANS. THE CONTRACTOR IS OBLIGATED TO PROVIDE ALL ITEMS/MATERIALS IN THE QUANTITIES SHOWN ON THE PLANS REGARDLESS OF WHETHER THEY ARE LISTED ON THE MATERIAL LIST.

MIG

MOORE IACOFANO GOLTSMAN, INC.
801 N. HARBOR BLVD.
FULLERTON, CA 92832
TEL 714/871-3538
FAX 714/871-1188
www.migcom.com

CONSULTANT:

PROJECT TEAM:
LANDSCAPE ARCHITECT
MIG INC.

ARCHITECT
PITASSI ARCHITECTS INC.

CIVIL ENGINEERS/SURVEYOR
WALDEN & ASSOCIATES

STRUCTURAL ENGINEERS
CORREIA CONSULTING & DESIGN

ELECTRICAL ENGINEERS
LRA ENGINEERS

IRRIGATION DESIGNER
WILLIAMS IRRIGATION DESIGN

GEOTECHNICAL ENGINEERS
CONVERSE CONSULTANTS

TURF GRASS CONSULTANT
GUISE AND ASSOCIATES

PERRIS VALLEY Big League Dreams

2155 Trumble Road
Perris, California, 92570

SHEET TITLE
NOTES, ABBREVIATIONS & MATERIALS LIST

100% CONSTRUCTION DOCUMENT

DATE	REVISIONS

STAMP

CHECKED BY	DATE
RE	
DATE 01-07-10	FILE NAME
DRAWN BY HD	SHEET LM-1
JOB NO. 05208.00	
SCALE 1"=30'-0"	188 OF 313 SHEETS