MATERIAL SCHEDULE

ITEM	MANUFACTURER	SPECIFICATION	CONTACT	NOTES
PRECAST DECORATIVE SIGN	QUICKCRETE PRODUCTS CORP.	MATERIAL: SRC USING BAKING SODA. TEXTURE: POCKETED FINISH. SEALER: 511. COLOR: C3-LATTE	951-737-6240	SUBMIT 5"x5" SAMPLE FOR APPROVAL PRIOR TO FABRICATION
DECORATIVE CONCRETE BASEBALL	QUICKCRETE PRODUCTS CORP.	QR36BB, COLOR: C-9 MISSION WHITE, FINISH: T-1 SMOOTH	951-737-6240	LOCATIONS PER PLANS
DECORATIVE WALL CAPS	QUICKCRETE PRODUCTS CORP.	Q-A135WC, COLOR: C3-LATTE, FINISH:T9 -SANDSTONE	951-737-6240	
BIG LEAGUE DREAMS LOGO PLAQUE FOR MONUMENT SIGN	ARTWORK TO BE SUPPLIED BY BIG LEAGUE DREAMS	¼" THK. STEEL LASER CUT LOGO. ATTACH TO WALL PER INDUSTRY STANDARDS.		SIGN SIZE APPROX. 2'-4" SQ.
FENCE CAP	TOMARK SPORTS	COLOR:TBD	800-959-1844	ALL 42" HIGH & 8' HIGH MINOR LEAGUE HOMERUN FENCING
DASHER WALL SYSTEM	SPORT SYSTEMS UNLIMITED	SEAMLESS INFINITY SERIES	877-778-5911	SEE SHEET LD-5.1 - LD-5.3
WAY-FINDING SIGN	QUICKCRETE PRODUCTS CORP.	REFER TO DETAIL 'J', SHEET LD-1.7.	951-737-6240	
ORNAMENTAL STEEL FENCE	AMERISTAR FENCE PRODUCTS	COLOR: MFG. BLACK FINISH	888-333-3422	
ORNAMENTAL STEEL VEHICULAR GATE	AMERISTAR FENCE PRODUCTS	COLOR: MFG. BLACK FINISH	888-333-3422	
ORNAMENTAL STEEL DOUBLE GATE	AMERISTAR FENCE PRODUCTS	COLOR: MFG. BLACK FINISH	888-333-3422	
ORNAMENTAL STEEL SINGLE GATE	AMERISTAR FENCE PRODUCTS	COLOR: MFG. BLACK FINISH	888-333-3422	
SOCCER TEAM BENCH	DANT-CLAYTON	MODEL: DTP-15 WITH POWDER COAT SEATS. COLOR: TBD	502-214-8709	
DECORATIVE PILASTER CAP	QUICKCRETE PRODUCT CORP.	Q-H36PC, COLOR: C3-LATTE, FINISH:T9 -SANDSTONE	951-737-6240	
REMOVABLE PITCHING RUBBER	ENDURO	TB-K10378	TOMARK SPORTS 800-959-1844	
DECORATIVE STONE VENEER	KRC ROCK	McGREGOR LAKE THIN VENEER FLATS #12VNR2790	760-744-1036 CONTACT: ISAAC HAUPU	SUBMIT SAMPLE APPROVAL PRIOR TO INSTALLATION.
DECORATIVE STONE VENEER CORNERS	KRC ROCK	McGREGOR LAKE THIN VENEER CORNERS	760-744-1036 CONTACT: ISAAC HAUPU	SUBMIT SAMPLE APPROVAL PRIOR TO INSTALLATION.
PORTABLE PROTECTIVE NETTING SYSTEMS	TOMARK SPORTS	8'X8' PRO NET SCREEN #TB-K12895 WITH 8" PNEUMATIC WHEELS	800-959-1844	PROVIDE (1) ONE NET FOR EACH BULLPEN, REFER TO PLANS

NOTE:
QUANTITIES AND MATERIALS PROVIDED ON THE MATERIAL LIST ARE FOR THE CONVENIENCE OF THE CONTRACTOR ONLY. ALL QUANTITIES AND MATERIALS SHOULD BE VERIFIED WITH THE PLANS. THE CONTRACTOR IS OBLIGATED TO PROVIDE ALL ITEMS/MATERIALS IN THE QUANTITIES SHOWN ON THE PLANS REGARDLESS OF WHETHER THEY ARE LISTED ON THE MATERIAL LIST.

CONSTRUCTION NOTES:

1. THE CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE AND FEDERAL GUIDELINES AND BUILDING CODES.
2. THE CONTRACTOR SHALL APPLY FOR, OBTAIN AND PAY FOR ALL REQUIRED PERMITS. PERMITS SHALL BE POSTED IAW LOCAL, STATE AND FEDERAL REGULATIONS.
3. ALL WORK, MATERIAL AND EQUIPMENT UTILIZED SHALL BE INSTALLED IN STRICT ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND SPECIFICATIONS.
4. ALL WORK FOR THIS PROJECT SHALL CONFORM TO STANDARDS PUBLISHED BY RECOGNIZED PROFESSIONAL AND INDUSTRY ORGANIZATIONS.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VISITING THE SITE PRIOR TO BIDDING AND SHALL FAMILIARIZE THEMSELVES WITH ALL EXISTING CONDITIONS AFFECTING THE WORK.
6. THE CONTRACTOR SHALL SUBMIT LUMP SUM PRICING FOR ENTIRE BID AND ADDITIVE ALTERNATES.
7. THE CONTRACTOR SHALL SEEK CLARIFICATION PRIOR TO BIDDING FROM THE LANDSCAPE ARCHITECT OF ANY DISCREPANCIES BETWEEN THE LANDSCAPE ARCHITECTURE, ARCHITECTURAL, CIVIL, ET AL DRAWINGS. THE MOST STRINGENT REQUIREMENTS SHALL APPLY.
8. THE CONTRACTOR SHALL SEEK CLARIFICATION PRIOR TO BIDDING OF ANY QUESTIONS CONCERNING CONDITIONS, DRAWINGS, DETAILS AND SPECIFICATIONS THAT WILL AFFECT SUBMISSION OF A COMPLETE AND ACCURATE BID.
9. THE CONTRACTOR SHALL OBTAIN WRITTEN APPROVAL FROM THE LANDSCAPE ARCHITECT AND OWNER FOR ANY DEVIATION FROM THE CONTRACT DOCUMENTS.
10. ALL REQUESTS FOR INFORMATION, CLARIFICATION, DEVIATION, OR SUBSTITUTION FOR ITEMS ON THE CONTRACT DOCUMENTS SHALL BE MADE IN WRITING THROUGH THE OWNER'S REPRESENTATIVE. THE LANDSCAPE ARCHITECT SHALL HAVE SEVEN (7) WORKING DAYS IN WHICH TO RESPOND.
11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREPARING AND MAINTAINING ALL CONSTRUCTION AREAS FREE OF DEBRIS AND HAZARDOUS MATERIALS THROUGHOUT THE CONSTRUCTION PROCESS.
12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR AND/OR REPLACEMENT OF ANY ITEMS/ AREAS DAMAGED DURING THE CONSTRUCTION PROCESS.
13. THE CONTRACTOR SHALL LAYOUT AND VERIFY ALL DIMENSIONS IN THE FIELD PRIOR TO THE START OF CONSTRUCTION. REPORT ANY DISCREPANCIES IMMEDIATELY TO THE LANDSCAPE ARCHITECT.
14. DIMENSIONS SHALL NOT BE SCALED FROM THE CONTRACT DOCUMENTS. DIMENSIONS SHOWN ON THE PLANS SHALL RULE. IN THE CASE OF AMBIGUITY THE CONTRACTOR SHALL REQUEST A CLARIFICATION OF DIMENSION FROM THE LANDSCAPE ARCHITECT.
15. WHERE THERE IS A DISCREPANCY BETWEEN THE QUANTITY SHOWN ON THE MATERIALS LIST AND THE QUANTITY SHOWN ON THE PLANS, THE PLANS SHALL RULE.
16. ALL DIMENSIONS SHOWN ARE FROM FINISH FACE TO FINISH FACE UNLESS OTHERWISE NOTED.

MIG

MOORE IACOFANO GOLTSMAN, INC.
801 N. HARBOR BLVD.
FULLERTON, CA 92832
TEL 714/871-3638
FAX 714/871-1188
www.migcom.com

CONSULTANT:

PROJECT TEAM:
LANDSCAPE ARCHITECT
MIG INC.
ARCHITECT
PITASSI ARCHITECTS INC.
CIVIL ENGINEERS/SURVEYOR
WALDEN & ASSOCIATES
STRUCTURAL ENGINEERS
CORREIA CONSULTING & DESIGN
ELECTRICAL ENGINEERS
LRA ENGINEERS
IRRIGATION DESIGNER
WILLIAMS IRRIGATION DESIGN
GEOTECHNICAL ENGINEERS
CONVERSE CONSULTANTS
TURF GRASS CONSULTANT
GUISE AND ASSOCIATES

PERRIS VALLEY Big League Dreams

2155 Trumble Road
Perris, California, 92570

SHEET TITLE
NOTES, ABBREVIATIONS & MATERIALS LIST

100% CONSTRUCTION DOCUMENT

DATE	REVISIONS

STAMP

CHECKED BY: RE
DATE:
DATE: 01-07-10
FILE NAME:
DRAWN BY: HD
SHEET: LM-2
JOB NO. 05208.00
SCALE 1"=30'-0"