SECTION 10501

WARDROBE LOCKERS

PART 1 - GENERAL

1.01 SUMMARY

A. Provide wardrobe lockers where shown on the Drawings, as specified herein, and as needed for a complete and proper installation.

B. Related work:
   1. Documents affecting work of this Section include, but are not necessarily limited to, General Conditions, Supplementary Conditions, and Sections In Division 1 of these Specifications.

C. Codes: Materials and work shall conform to the governing Building Code. In case of conflict between these Specifications, the standard specifications, and the Building Code, the more stringent shall govern.

1.02 SUBMITTALS

A. Comply with pertinent provisions of Section 01300.
B. Product data: Within 45 calendar days after the Contractor has received the Owner's Notice to Proceed, submit:
   1. Materials list of items proposed to be provided under this Section;
   2. Manufacturer's specifications and other data needed to prove compliance with the specified requirements;
   3. Color chips showing the specified color; do not provide manufacturers catalogs without indicating selected colors. Proper color selection must be indicated for verification by architect.
   4. Manufacturer's recommended installation procedures which, when approved by the Architect, will become the basis for accepting or rejecting actual installation procedures used on the Work.

1.03 QUALITY ASSURANCE

A. Use adequate numbers of skilled workmen who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and the methods needed for proper performance of the work of this Section.

1.04 DELIVERY, STORAGE, AND HANDLING

A. Comply with pertinent provisions of Section 01600.

PART 2 – PRODUCTS

2.01 LOCKERS AND BENCHES

A. Wardrobe Lockers: Provide products of Republic Storage Systems Company, 1038 Belden Avenue NE, Clayton, Ohio 44705 (800) 477-1255, or equal.
   1. Use all metal construction, and finish in manufacturers standard color "#83 Decorator Tan."

2. Each locker shall be a finished and complete piece with top, bottom, back and sides to form a single unit.
3. Provide standard double tier metal lockers which shall each be 12" wide, 18" deep and 36" high (for a total height of 72") and shall have the following amenities:
   a. Provide sloping tops and corner closure sloping tops.
   b. Provide aluminum number plates with etched figures 3/8" high. Number 1-14.
   c. Lockers shall be anchored at the floor and wall per the approved Shop Drawings.
   d. All steel parts shall be thoroughly cleaned, given a bonding and rust-inhibitive phosphate treatment and a heavy coat of high-quality enamel. Enamel shall be baked on and must withstand a rigid hammer test without chipping or flaking. Complete locker must be finished in the same color.
   e. All components of the locker shall be of the gauge and quality indicated in the standard specifications of the manufacturer. Minimum 18 gauge.
   f. A minimum of one locker in each Locker Room shall be fully accessible and comply with ADA, and the C.B.C.

2.02 OTHER MATERIALS

A. Provide other materials, not specifically described but required for a complete and proper installation, as selected by the Contractor subject to the approval of the Architect.

PART 3 – EXECUTION

3.01 SURFACE CONDITIONS

A. Examine the areas and conditions under which work of this Section will be performed. Correct conditions detrimental to timely and proper completion of the Work. Do not proceed until unsatisfactory conditions are corrected.

3.02 INSTALLATION

A. Install the work of this Section where shown on the Drawings and in strict accordance with the manufacturer's installation recommendations as approved by the Architect, anchoring firmly into position for long life under hard use.

END OF SECTION - 10501

SECTION 10520

FIRE EXTINGUISHERS AND CABINETS

PART 1 - GENERAL

1.01 SUMMARY

A. Provide fire extinguishers and cabinets where shown on the Drawings, as specified herein, and as needed for a complete and proper installation.

B. Related work:
   1. Documents affecting work of this Section include, but are not necessarily limited to, General Conditions, Supplementary Conditions, and Sections in Division 1 of these Specifications.

C. Codes: Materials and work shall conform to the governing Building Code. In case of conflict between these specifications, the standard specifications, and the Building Code, the more stringent shall govern.

1.02 SUBMITTALS

A. Comply with pertinent provisions of Section 01300.

B. Product data: Within 45 calendar days after the Contractor has received the Owner's Notice to Proceed, submit:
   1. Materials list of items proposed to be provided under this Section;
   2. Manufacturer's specifications and other data needed to prove compliance with the specified requirements;
   3. Dimensioned drawings as needed to depict the space required for these items, and their interface with the work of other trades.
   4. Manufacturer's recommended installation procedures which, when approved by the Architect, will become the basis for accepting or rejecting actual installation procedures used on the Work.

1.03 QUALITY ASSURANCE

A. Use adequate numbers of skilled workmen who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and the methods needed for proper performance of the work of this Section.

1.04 DELIVERY, STORAGE, AND HANDLING

A. Comply with pertinent provisions of Section 01600.

PART 2 - PRODUCTS

2.01 CABINETS

A. Where shown on the Drawings, provide J.L. Industries "Panorama 1037 C-71" factory prefinished semi-recessed steel cabinets with stainless steel trim. Provide the "Panorama 1035 C-71" fully recessed unit when mounted in a 6" stud wall or furred wall recess. Provide the "Panorama 1033 C-71" when surface mounted on a masonry wall.

B. Equal products by other manufacturers shall be considered under the provisions of Section 01300.

2.02 FIRE EXTINGUISHERS

A. At each fire extinguisher cabinet, provide one multi-purpose chemical fire extinguisher with UL rating of 2A-10B,C J.L. Industries, Model "Cosmic 5-E". Fire extinguisher location is subject to approval by the Riverside County Fire Department.

B. Service, charge, and tag each fire extinguisher not more than five calendar days prior to the Date of Substantial Completion of the Work as that Date is established.

PART 3 - EXECUTION

3.01 SURFACE CONDITIONS

A. Examine the areas and conditions under which work of this Section will be performed. Correct conditions detrimental to timely and proper completion of the Work. Do not proceed until unsatisfactory conditions are corrected.

3.02 INSTALLATION

A. Coordinate as required with other trades to assure proper and adequate provision in the work of those trades for interface with the work of this Section.

B. Install the work of this Section in strict accordance with the original design, the approved Shop Drawings, pertinent requirements of governmental agencies having jurisdiction, and the manufacturer's recommended installation procedures as approved by the Owner, anchoring all components firmly into position for long life under hard use.

END OF SECTION - 10520