SECTION 10165

TOILET PARTITIONS

PART 1 - GENERAL

1.01 SUMMARY

A. Provide toilet partitions where shown on the Drawings, as specified herein, and as needed for a complete and proper installation.

B. Related work:
   1. Documents affecting work of this Section include, but are not necessarily limited to, General Conditions, Supplementary Conditions, and Sections in Division 1 of these Specifications.

1.02 SUBMITTALS

A. Comply with pertinent provisions of Section 01300.

B. Product data: Within 30 calendar days after the Contractor has received the Owner's Notice to Proceed, submit:
   1. Materials list of items proposed to be provided under this Section;
   2. Manufacturer's specifications and other data needed to prove compliance with the specified requirements;
   3. Shop Drawings in sufficient detail to show fabrication, installation, anchorage, and interface of the work of this Section with the work of adjacent trades;
   4. Color and pattern charts showing colors and patterns available in the specified products from the proposed manufacturer.
   5. Manufacturer's recommended installation procedures which, when approved by the Architect, will become the basis for accepting or rejecting actual installation procedures used on the Work.

1.03 QUALITY ASSURANCE

A. Use adequate numbers of skilled workmen who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and the methods needed for proper performance of the work of this Section.

1.04 DELIVERY, STORAGE, AND HANDLING

A. Comply with pertinent provisions of Section 01600.

PART 2 - PRODUCTS

2.01 TOILET PARTITIONS

A. Provide Scranton Products High-Density Polyethylene toilet partitions, floor mounted with overhead brace, as shown on the Drawings. Equal products of other manufacturers, approved in advance by the Architect, shall be considered. Provide dimensions, arrangements, and finishes shown on the Drawings. Color shall be as shown on the Drawings.

B. Manufacturer shall be Scranton Products, 801 Corey St., Moosic, PA 18507. (800) 445-5148, Fax: (800) 551-6993. www.scrantonproducts.com

PART 3 - EXECUTION

3.01 SURFACE CONDITIONS

A. Examine the areas and conditions under which work of this Section will be performed. Correct conditions detrimental to timely and proper completion of the Work. Do not proceed until unsatisfactory conditions are corrected.

3.02 INSTALLATION

A. Coordinate as required with other trades to assure proper and adequate provision in the work of those trades for interface with the work of this Section.

B. Install the work of this Section in strict accordance with the original design, the approved Shop Drawings, pertinent requirements of governmental agencies having jurisdiction, and the manufacturer's recommended installation procedures as approved by the Architect, anchoring all components firmly into position for long life under hard use.

C. Install compartments in rigid, straight, plumb and level manner.

D. All doors and panels to be mounted at 14" above finished floor.

E. Adjust doors, except doors to handicapped compartments, to remain at a uniformly open position when unlocked.

F. Scratches and abrasions to be completely invisible to the unaided eye from a distance of five feet.

END OF SECTION - 10165