SECTION 10001

MISCELLANEOUS ITEMS

PART 1 - GENERAL

1.01 SUMMARY

A. Furnish materials and perform labor required to execute this work as indicated on the Drawings, as specified and as necessary to complete the Contract, including, but not limited to, these major items:
   1. Countertop support brackets.
   2. Bar footrails.
   3. Slat Wall panels.

1.02 GENERAL REQUIREMENTS

A. Codes: Materials and work shall conform to the governing Building Code. In case of conflict between these specifications, the standard specifications, and the Building Code, the more stringent shall govern.

B. Shop Drawings: Submit in accordance with Shop Drawings and Samples Section 01300, showing in complete detail all information required for fabrication, finishing and installation of this work.

1.03 DELIVERY, STORAGE, AND HANDLING

A. Comply with pertinent provisions of Section 01600.

PART 2 - PRODUCTS

2.01 MATERIALS

A. Counter Supports: Provide flush-mount "L"-shaped supports as manufactured by Rakks/ Rangine Corporation, 330 Reservoir St., Needham, MA 02494, or equal, as called for on plans.
   1. Counter supports shall be of 6063-T6 extruded aluminum, TIG welded along mitered sides and back, with factory drilled holes for mounting. Supports shall be factory primed for field painting as shown on the plans.

B. Bar Footrail: Provide Bar Footrail as manufactured by The Wagner Companies, 10600 West Brown Deer Rd., Milwaukee, WI, 53224, or equal.
   1. Provide Bar Footrail Combination Bracket #142061, with Brass finish and 2" tube.
   2. Provide steel internal reinforcing bars, elbows, angles, fittings, end caps, and other components to make a complete and functional installation.

C. Slat Wall: Provide slatwall with routed horizontal grooves at 4" on center in 4' wide by 8' high panels. Face of panels shall be covered with high-pressure plastic laminate, color as shown on Drawings. Provide aluminum channels for display hardware at grooves. Mount panels per manufacturer's instructions.

PART 3 - EXECUTION

3.01 INSTALLATION

A. Install all items in accordance with manufacturer's recommendations and Architect reviewed Shop Drawings. Insure that all items with moving parts operate smoothly. Anchor all components firmly into position for long life under hard use.

END OF SECTION - 10001